

construction  
engineering  
research  
laboratory




United States Army  
Corps of Engineers  
... Serving the Army  
... Serving the Nation

TECHNICAL REPORT M-279  
May 1980

ROOFING REPAIR MATERIALS FOR KOREAN  
RELOCATABLE BUILDINGS—TEST AND EVALUATION

ADA 085188



by  
Robert E. Muncy

DTIC  
ELECTE  
JUN 9 1980  
A



80 6 6 096

Approved for public release; distribution unlimited.

DDC FILE CO

The contents of this report are not to be used for advertising, publication, or promotional purposes. Citation of trade names does not constitute an official indorsement or approval of the use of such commercial products. The findings of this report are not to be construed as an official Department of the Army position, unless so designated by other authorized documents.

**DESTROY THIS REPORT WHEN IT IS NO LONGER NEEDED  
DO NOT RETURN IT TO THE ORIGINATOR**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER (14) CERL-TR-M-279	2. GOVT ACCESSION NO. AD-A085188	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) (6) ROOFING REPAIR MATERIALS FOR KOREAN RELOCATABLE BUILDINGS - TEST AND EVALUATION		5. TYPE OF REPORT & PERIOD COVERED (9) FINAL Repts
7. AUTHOR(s) (10) Robert E. Muncy		8. CONTRACT OR GRANT NUMBER(s) IAO No. FED 3-80
9. PERFORMING ORGANIZATION NAME AND ADDRESS US ARMY CONSTRUCTION ENGINEERING RESEARCH LABORATORY P.O. Box 4005, Champaign, IL 61820		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS (12) 171
11. CONTROLLING OFFICE NAME AND ADDRESS		12. REPORT DATE (11) May 80
		13. NUMBER OF PAGES 15
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report)  Approved for public release; distribution unlimited.		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES  Copies are obtainable from National Technical Information Service Springfield, VA 22151		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number)  roofs repair		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number)  This report presents the results of tests of two commercial roof repair materials, Contourflash and Polyseal, to determine how they would perform in the roof repair of Army relocatable barracks in Korea. All tests were conducted with the existing roof sealant in place.		

## FOREWORD

This investigation was conducted for the Far East Division (FED), U.S. Army Corps of Engineers, at the request of the Pacific Ocean Division (POD), under Intra-Army Order (IAO) No. FED 3-80. The Point of Contact at POD was Mr. A. D. Sameshima.

The work was performed by the Engineering and Materials (EM) Division, U.S. Army Construction Engineering Research Laboratory (CERL). Dr. G. R. Williamson is Chief of EM.

COL L. J. Circeo is Commander and Director of CERL and Dr. L. R. Shaffer is Technical Director.

ACCESSION FOR	
NTIS	<input checked="checked" type="checkbox"/>
DDC	<input type="checkbox"/>
Unpublished	<input type="checkbox"/>
Classification	
By _____	
Date _____	
Project No. _____	
Title/Description _____	
Dist	Special
A	

## CONTENTS

DD FORM 1473	1
FOREWORD	3
LIST OF FIGURES	5
1 INTRODUCTION .....	7
Background	
Objective	
Approach	
Scope	
Safety	
2 TEST PROGRAM AND RESULTS .....	7
Specimen Preparation (Substrate)	
Test Materials	
Curing	
Cyclic Loading Tests	
Tensile Strength and Elongation Tests	
Hardness Tests	
Adhesion Tests	
Ultraviolet Exposure	
3 CONCLUSIONS AND RECOMMENDATIONS .....	15
Conclusions	
Recommendations	
DISTRIBUTION	

## FIGURES

Number	Page
1 Bond Breaker	8
2 Polyseal Adhesion Specimen	8
3 Bondbreaker Under Contourflash	10
4 Adaptation of Test Machine for Temperature Control	10
5 Tensile Test Machine	11
6 Tear in Polyseal	11
7 Enlarged Tear in PS-5	13
8 Maximum Gap Between Test Coupons	13
9 Backer Rod of Foam	14
10 Typical Failure of Repair Material Adhesion	14

# ROOFING REPAIR MATERIALS FOR KOREAN RELOCATABLE BUILDINGS—TEST AND EVALUATION

## 1 INTRODUCTION

### Background

Two hundred and forty "relocatable" panel barracks, each 24 X 48 ft (7.3 X 14.6 m), were built at U.S. Army installations in Korea during FY75 and FY76. The roofs on these barracks were designed for panel-to-panel connections; through the years, the environment has begun to affect the soft sealant exposed in these connections, causing leaks to develop in some roofs. These leaks are sometimes enlarged when troops walk on the roofs.

In January 1980, the Corps of Engineers' Pacific Ocean Division (POD) asked the U.S. Army Construction Engineering Research Laboratory (CERL) to evaluate two potential roof repair materials: Contourflash and Polyseal.\* Both materials are compounded forms of chloroprene (neoprene) rubber. Contourflash is supplied in sheet form and is designed to cure slowly after application. Polyseal is a trowel-applied mastic from which solvent evaporates, leaving solid material which cures into a rubber.

### Objective

The objective of this study was to evaluate the potential of Contourflash and Polyseal as roof repair materials for Army relocatable barracks in Korea.

### Approach

1. The effects of temperature changes and live loads on the roofs of relocatable buildings were simulated.
2. The effects of temperature on the repair materials and the adhesive bond to the metal roof panels were determined.
3. The effects of ultraviolet exposure on cured Contourflash and Polyseal were examined.

\*Contourflash is a product of Gaco Western, Inc., P.O. Box 88698, Seattle, WA; Polyseal is a product of the Monroe Company, Inc., 30801 Carter Street, Cleveland, OH.

### Scope

This study was limited to the two material systems specified to CERL by POD.

### Safety

The solvents contained in Contourflash and Polyseal should not adversely affect personnel when used in an adequately ventilated area. Since some of the solvent materials are flammable, a "no smoking" or "no open flame" policy should be used during application.

## 2 TEST PROGRAM AND RESULTS

Both Polyseal and Contourflash were evaluated based on how they performed when applied over the existing roof sealant, a material called Superseal.

### Specimen Preparation (Substrate)

Each specimen was prepared using two 4 X 4 in. (101.6 X 101.6 mm) coupons taken from roof panels similar to those in actual use on roofs in Korea. All coupons were 0.025-in. (0.635-mm)-thick painted embossed aluminum loosely attached to 1/2-in. (12.7-mm) plywood. The coupons' surfaces were prepared by first washing the painted aluminum, then cleaning it by rubbing lightly with a clean cloth and xylene, a grease and oil solvent.

### Test Materials

The Polyseal was applied by trowelling a strip about 1/4 X 6-1/2 in. (6.35 X 165.1 mm) thick over a 4-in. (10.6-mm)-wide strip of Superseal. A 1-in. (25.4-mm)-wide bond breaker of teflon tape was placed on the Superseal before the Polyseal was applied (Figure 1). The tape was centered over the length of the panel joint. These specimens were later used for tensile strength, elongation, and cyclic stretching tests. Because it was difficult to trowel and smooth the Polyseal, all Polyseal test specimens (Figure 2) were of uneven material thickness.

Contourflash specimens were 4 in. (101.6 mm) wide X 7 in. (177.8 mm) long and were prepared in three ways:

1. The bonding area of each coupon was coated with Gaco Western epoxy E-5320 and allowed to cure overnight at room temperature. Contact cement (Gaco N-7R) was then applied to both the epoxy-primed area and the Contourflash. The solvent from the contact



Figure 1. Bond breaker.



Figure 2. Polyseal adhesion specimen.



cement was allowed to evaporate for about 30 minutes, then a 1-in. (25.4-mm)-wide strip of teflon tape was placed over the joint and the surfaces were bonded together (Figure 3).

2. Another group of Contourflash specimens were prepared exactly as described above, except Gaco Western epoxy E-5320 was not used.

3. The adhesion test specimens were prepared by applying a 4-in. (101.6-mm)-wide strip of Contourflash to a 4 X 4 1/2 in. (101.6 X 114.3 mm) coupon. After curing, the rubber was slit into 1-in. (25.4-mm)-wide strips. No difficulty in applying the material was experienced with either procedure.

#### **Curing**

The Polyseal specimens were cured at a room temperature of about 70°F (21.1°C) for 48 hours. The specimens were then placed in an oven and heated to 150°F (65.6°C) for 72 hours, and to 200°F (93.3°C) for 16 hours. (The Superseal did not appear to be affected by sustained elevated temperatures.)

The Contourflash specimens were cured at about 70°F (21.1°C) for 24 hours, then placed in an oven and heated to 150°F (65.6°C) for 72 hours, and to 200°F (93.3°C) for 16 hours.

#### **Cyclic Loading Tests**

Tests were conducted at low and high temperatures (-40 and 165°F [-40 and 73.9°C], respectively) to determine (1) the ability of Polyseal and Contourflash to withstand elongation, (2) the quality of their adhesive bond to the aluminum, and (3) their durability under cyclic loading. The equipment setup for the endurance test is shown in Figure 4; the setup for the elongation test is shown in Figure 5.

For the loading tests, cyclic loading at a frequency of 1 cycle/second (cps) and a stroke of 3/8 in. (9.5 mm) was used. The stroke was selected to be about the same as the maximum movement during extreme temperature changes.

#### **Polyseal Cyclic Loading Tests**

Six Polyseal specimens (labeled PS-1, PS-2, etc.) were subjected to cyclic loading.

Specimen PS-1 was tested at -25°F (-31.7°C) and 1 cps for 450 cycles; the PS-1 test was continued as the chamber temperature increased from -25 to 45°F (-31.7 to 7.22°C), at which time 1850 cycles had been

completed. The test continued as the temperature gradually rose to 60°F (15.6°C). A total of 8000 cycles were completed. The temperature rise occurred because of a loss of cooling capacity, a condition that was subsequently corrected. The test was terminated with no visible discontinuities. It was noted that the elongation recovery of the Polyseal specimens at -25°F (-31.7°C) was not complete within each cycle.

PS-1 was later tested at 165°F (73.9°C) and 1 cps; the material recovered almost completely during each cycle. After 600 cycles at this new temperature, the adhesion bond near one edge of the specimen began to fail; i.e., it pulled away from the aluminum. The PS-1 test was discontinued after 685 cycles when the Polyseal completely separated from one of the aluminum coupons.

Specimen PS-2 was tested at -40°F (-40°C) for 270 cycles, at which time repeated localized bending caused the thin aluminum facing to break.

Specimen PS-3 was tested at -40°F (-40°C). At 660 cycles, a 3/4-in. (19.05-mm)-long tear started near the center of the PS-3 specimen over the coupon joint. A small tear became visible at the right edge of the specimen after 760 cycles (Figure 6). After 850 cycles, the tape (bond breaker) was visible through the Polyseal and the test was discontinued.

Specimen PS-5 was tested at -40°F (-40°C). A tear became visible at 800 cycles; at 1150 cycles, the tear extended halfway across the specimen. However, when the test was terminated at 1930 cycles, the tear still was not completely across the material (Figure 7).

Specimen PS-6 was tested at -40°F (-40°C). The first 10 cycles were run at 100 seconds/cycle and the material recovered completely at this loading/unloading rate. The test was completed by switching the rate to 1 cps, and after 100 cycles, the aluminum failed by bending.

#### **Contourflash Cyclic Loading Tests**

Three Contourflash specimens (labeled C-1, C-2, and C-3) were evaluated for cyclic loading performance.

Specimen C-1 was tested at -39°F (-39.4°C) for 1090 cycles with no failure. The test was continued by increasing the temperature from -39 to 0°F (-39.4 to -17.8°C); at 1806 cycles there was no failure. A final extension of the test from 0 to 30°F (-17.8 to




Figure 3. Bondbreaker under Contourflash.



Figure 4. Adaptation of test machine for temperature control.




Figure 5. Tensile test machine.



Figure 6. Tear in Polyseal (arrow).

1.1°C) and 3206 cycles produced no visible discontinuities or failure.

Specimen C-2 was tested at -38°F (-38.8°C) to 4000 cycles with no failure. The test was extended by increasing the temperature from -38 to -8°F (-38.8 to -22.2°C) for 5035 cycles; there was no failure.

Specimen C-3 was tested at 165°F (73.9°C) for 6000 cycles with no visible discontinuities.

Displacement in all three Contourflash tests was 3/8 in. (9.5 mm) (Figure 8).

#### Tensile Strength and Elongation Tests

In the tensile strength and elongation tests, a load rate of 1 in. (25.4 mm) per minute was used. One Polyseal and four Contourflash specimens were tested. Contourflash coupons C-6 and C-7 (Figure 9) used a backer rod to increase the length of material that was not bonded to the substrate and that could, therefore, be involved in stretching. The test results are described below.

Coupon C-4, tested at about -40°F (-40°C), had a tensile strength greater than 880 psi (5.06 MPa) and elongation greater than 1 in. (25.4 mm) (more than 100 percent) before adhesive bond slippage began. Coupon C-4 was prepared using N-7R adhesive plus E-5320 epoxy.

Coupon C-5, tested at about -40°F (-40°C), had a tensile strength greater than 1160 psi (27.99 MPa) and elongation greater than 1 in. (25.4 mm) (more than 100 percent) before adhesive debonding from the aluminum began. This specimen did not include the epoxy primer.

Coupons C-6 and C-7 were tested at 70°F (21.1°C) and both had an elongation greater than 1 in. (25.4 mm) (100 percent) and tensile strengths of greater than 520 and 680 psi (3.5 and 4.68 MPa), respectively. The inclusion of the backer rod did not significantly add to the performance of the material.

Coupon PS-7 (Polyseal) was tested at -40°F (-40°C); it showed a tensile strength greater than 760 psi (5.2 MPa) and a total of 1-5/8 in. (41.3 mm) (160 percent) elongation before failure (Figure 10). All elongation test specimens experienced lap shear failure in the adhesive bond. The failure proceeded as a line from the joint toward the grip ends of the coupons.

#### Hardness Tests

Hardness tests were performed in accordance with ASTM D 2240-75 using a Shore A-2 Durometer tester.<sup>1</sup> The results were:

Contourflash	Polyseal
Hardness of 90 at -40°F (-40°C)	Hardness of 95+ at -40°F (-40°C)
Hardness of 70 at 70°F (21.1°C)	Hardness of 80 at 70°F (21.1°C)
Hardness of 68 at 74°F (23.3°C)	Hardness of 60 at 74°F (23.3°C)

The increase in hardness at the low temperature is normal and suggests the approach of the temperature at which the material would be brittle.

#### Adhesion Tests

Adhesion tests were performed in accordance with ASTM D 429-73.<sup>2</sup> The results of these tests are described below.

1. Polyseal at 70°F (21.1°C): All four test specimens failed at 5 lb/in. (2.27 kg/25.4 mm) of width and failed at the Polyseal-paint interface.

2. Contourflash with N-7R adhesive only at 70°F (21.1°C):

Result	Comment
Specimen 1: 8 lb/in. (3.64 kg/25.4 mm) of width	Adhesive pulled away from painted metal surface
Specimen 2: 9 lb/in. (4.09 kg/25.4 mm) of width	
Specimens 3, 4: 12 lb/in. (5.45 kg/25.4 mm) of width	

3. Contourflash with N-7R adhesive plus E-5320 epoxy tested at 70°F (21.1°C):

Result	Comment
Specimen 1: 14 lb/in. (6.36 kg/25.4 mm) of width	Separation was within the N-7R layer
Specimen 2: 13 lb/in. (5.9 kg/25.4 mm) of width	
Specimen 3: 13-1/2 lb/in. (6.14 kg/25.4 mm) of width	

<sup>1</sup>Rubber Property—Test for Durometer Hardness, ASTM D 2240-75 (American Society for Testing and Materials [ASTM], 1973).

<sup>2</sup>Rubber Property—Tests for Adhesion to Rigid Substrates, ASTM D 429-73 (ASTM, 1975).




Figure 7. Enlarged tear in PS-5.



Figure 8. Maximum gap between test coupons.



**Figure 9. Backer rod of foam.**



**Figure 10. Typical failure of repair material adhesion.**

#### **Ultraviolet Exposure**

Four samples (two Contourflash, two Polyseal) were prepared and subjected to ultraviolet light and water condensation for 1224 hours. An Atlas UV-Con system was set at a 50 percent ultraviolet -50 percent condensation cycle for the test. A slightly sooty discoloration of the Contourflash was noted; this discoloration could not be removed by rubbing it lightly by hand. A hardness reading was taken at 70°F (21.1°C) using the Shore A-2 Durometer. The Contourflash samples registered a hardness value of 76; the Polyseal samples recorded a value of 80. These results indicated a slight increase in hardness of the Contourflash under the conditions and no observable hardness change in the Polyseal. The slight hardness change in the Contourflash was not regarded as significant.

### **3 CONCLUSIONS AND RECOMMENDATIONS**

#### **Conclusions**

##### *Cyclic Loading*

Five of the six Polyseal test specimens subjected to different cyclic loading rates and different temperatures failed or exhibited discontinuities. None of the three Contourflash specimens tested failed or exhibited discontinuities.

##### *Tensile Strength and Elongation*

The Polyseal specimen exhibited a tensile strength greater than 760 psi (5.2 MPa) before failure. The Contourflash specimens exhibited tensile strengths ranging from greater than 520 psi (3.5 MPa) at 70°F (21.1°C) to 1160 psi (27.99 MPa) at -40°F (-40°C).

Elongation in the Polyseal specimen was greater than 1-5/8 in. (41.3 mm) or more than 160 percent. Elongation in the Contourflash specimens was greater than 1 in. (25.4 mm) or more than 100 percent in all tests.

#### **Hardness**

Polyseal specimens had a hardness of more than 95 at -40°F (-40°C), 80 at 70°F (21.1°C), and 60 at 74°F (23.3°C). Contourflash specimens had a hardness of 90 at -40°F (-40°C), 70 at 70°F (21.1°C), and 68 at 74°F (23.3°C).

#### **Adhesion**

All Polyseal test specimens failed at 5 lb/in. (2.27 kg/15.4 mm). Contourflash specimens with N-7R adhesive failed at 8, 9, and 12 lb/in. (3.64, 4.09, and 5.45 kg/25.4 mm); the Contourflash specimen with E-5320 epoxy failed between 13 and 14 lb/in. (5.9 and 6.36 kg/25.4 mm).

#### **Ultraviolet**

Exposure to ultraviolet light and water condensation produced an insignificant increase in the hardness of the Contourflash specimens; there was no observable change in Polyseal hardness during the tests.

#### **Recommendations**

1. A minimum bonding area 2 in. (50.8 mm) wide should be allowed on each side of the existing Superseal when the repair material is applied.
2. Special attention should be paid to the surface preparation and the application of the repair material. The quality of these two features is critical to obtaining satisfactory long-term leak protection.
3. Personnel should be kept off relocatable panel barrack roofs except for required work, and then only with load-spreading walkways in place.

# CERL DISTRIBUTION

Chief of Engineers  
ATTN: Tech Monitor  
ATTN: DAEN-RD  
ATTN: DAEN-MP  
ATTN: DAEN-ZC  
ATTN: DAEN-CW  
ATTN: DAEN-RM  
ATTN: DAEN-CCP  
ATTN: DAEN-ASI-L (2)

## US Army Engineer Districts

ATTN: Library  
Alaska  
Albaton  
Albuquerque  
Baltimore  
Buffalo  
Charleston  
Chicago  
Detroit  
Far East  
Fort Worth  
Galveston  
Huntington  
Jacksonville  
Japan  
Jidda  
Kansas City  
Little Rock  
Los Angeles  
Louisville  
Memphis  
Mobile  
Nashville  
New Orleans  
New York  
Norfolk  
Omaha  
Philadelphia  
Pittsburgh  
Portland  
Riyadh  
Rock Island  
Sacramento  
San Francisco  
Savannah  
Seattle  
St. Louis  
St. Paul  
Tulsa  
Vicksburg  
Walla Walla  
Wilmington

## US Army Engineer Divisions

ATTN: Library  
Europe  
Huntsville  
Lower Mississippi Valley  
Middle East  
Middle East (Rear)  
Missouri River  
New England  
North Atlantic  
North Central  
North Pacific  
Ohio River  
Pacific Ocean  
South Atlantic  
South Pacific  
Southwestern

## Waterways Experiment Station

ATTN: Library

## Cold Regions Research Engineering Lab

ATTN: Library

## US Government Printing Office

Receiving Section/Depository Copies (2)  
Defense Technical Information Center  
ATTN: DDA (12)

## Engineering Societies Library

New York, NY

## FESA, ATTN: Library

## ETL, ATTN: Library

## Engr. Studies Center, ATTN: Library

## Inst. for Water Res., ATTN: Library

## Army Instl. and Major Activities (COMUS)

DARCOM - Dir., Inst., & Svcs.  
ATTN: Facilities Engineer  
ARRADCOM  
Aberdeen Proving Ground  
Army Matls. and Mechanics Res. Ctr.  
Corpus Christi Army Depot  
Harry Diamond Laboratories  
Dugway Proving Ground  
Jefferson Proving Ground  
Fort Monmouth  
Letterkenny Army Depot  
Natick Research and Dev. Ctr.  
New Cumberland Army Depot  
Pueblo Army Depot  
Red River Army Depot  
Redstone Arsenal  
Rock Island Arsenal  
Savannah Army Depot  
Sharpe Army Depot  
Seneca Army Depot  
Tobyhanna Army Depot  
Tooele Army Depot  
Watervliet Arsenal  
Yuma Proving Ground  
White Sands Missile Range

## FORSCOM

FORSCOM Engineer, ATTN: AFEN-FE  
ATTN: Facilities Engineers  
Fort Buchanan  
Fort Bragg  
Fort Campbell  
Fort Carson  
Fort Devens  
Fort Drum  
Fort Hood  
Fort Indiantown Gap  
Fort Irwin  
Fort Sam Houston  
Fort Lewis  
Fort McCoy  
Fort McPherson  
Fort George G. Meade  
Fort Ord  
Fort Polk  
Fort Richardson  
Fort Riley  
Presidio of San Francisco  
Fort Sheridan  
Fort Stewart  
Fort Wainwright  
Vancouver Bks.

## TRADOC

HQ, TRADOC, ATTN: ATEN-FE  
ATTN: Facilities Engineer  
Fort Belvoir  
Fort Benning  
Fort Bliss  
Carlisle Barracks  
Fort Chaffee  
Fort Dix  
Fort Eustis  
Fort Gordon  
Fort Hamilton  
Fort Benjamin Harrison  
Fort Jackson  
Fort Knox  
Fort Leavenworth  
Fort Lee  
Fort McClellan  
Fort Monroe  
Fort Rucker  
Fort Sill  
Fort Leonard Wood

## INSCOM - Ch. Instl. Div.

ATTN: Facilities Engineer  
Vint Hill Farms Station  
Arlington Hall Station

## WESTCOM

ATTN: Facilities Engineer  
Fort Shafter

## MDW

ATTN: Facilities Engineer  
Cameron Station  
Fort Lesley J. McNair  
Fort Myer

## HSC

HQ USAHSC, ATTN: HSLO-F  
ATTN: Facilities Engineer  
Fitzsimons Army Medical Center  
Walter Reed Army Medical Center

## USACC

ATTN: Facilities Engineer  
Fort Huachuca  
Fort Ritchie

## MTMC

HQ, ATTN: MTMC-SA  
ATTN: Facilities Engineer  
Oakland Army Base  
Bayonne MOT  
Sunny Point MOT

## US Military Academy

ATTN: Facilities Engineer

## USAES, Fort Belvoir, VA

ATTN: FE Mgmt. Br.  
ATTN: Const. Mgmt. Br.  
ATTN: Engr. Library

## Chief Inst. Div., IBSA, Rock Island, IL

USA ARRCOM, ATTN: Dir., Instl & Svc  
TARCOM, Fac. Div.  
TECOM, ATTN: DRSTE-LG-F  
TSARCOM, ATTN: STSAS-F  
NARAD COM, ATTN: DRDMA-F  
AMMRC, ATTN: DRAMR-ME

## HQ, XVIII Airborne Corps and Ft. Bragg

ATTN: AFZA-FE-EE

## HQ, 7th Army Training Command

ATTN: AETTG-DEH (5)

## HQ USAREUR and 7th Army

ODCS/Engineer  
ATTN: AEAE-EN (4)

## V Corps

ATTN: AETVDEH (5)

## VII Corps

ATTN: AETSDEH (5)

## 21st Support Command

ATTN: AEREH (5)

## US Army Berlin

ATTN: AEBA-EN (2)

## US Army Southern European Task Force

ATTN: AESE-ENG (5)

## US Army Installation Support Activity, Europe

ATTN: AEUES-RP

## 8th USA, Korea

ATTN: EAFE  
Cdr, Fac Engr Act (8)  
AFE, Yongsan Area  
AFE, 20 Inf Div  
AFE, Area II Spt Det  
AFE, Cp Humphreys  
AFE, Pusan  
AFE, Taegu

## DLA ATTN: DLA-WI

USA Japan (USARJ)  
Ch. FE Div, AJEN-FE  
Fac Engr (Monshu)  
Fac Engr (Okinawa)

## ROK/US Combined Forces Command

ATTN: EUSA-HHC-CFC/Engr



Muncy, Robert E.

Roofing repair materials for Korean relocatable buildings : test and evaluation. --  
Champaign, IL : Construction Engineering Research Laboratory ; Springfield, VA :  
available from NTIS, 1980.  
15 p. (Technical report ; M-279)

1. Roofs -- maintenance and repair. I. Title. II. Series: U.S. Army  
Construction Engineering Research Laboratory. Technical report ; M-279.